

Gibbsland Bank clarifications:

1. The light fixture shown on detail A/A1.03 shall be as follows: eleven(11) Lithonia C132-48" and two(2) Lithonia C172-72" strip lights. Provide wall switch at same location of switches shown on sheet E1. Circuit to 20A/1P breaker in panel "L".
2. The solid oak topper on the teller stations shall be 5/4" solid oak topper in lieu of ¾".
3. Any mention of The State of Louisiana in the specifications is erroneous, the owner is Gibbsland Bank & Trust.
4. The client will not occupy at any time a part of the building during the course of construction.
5. On Drawing Sheet B (at the dumpster pad) the note in the box that states to install a floor drain and tie into the grease interceptor is an erroneous statement and is not part of this project.
6. In Supplementary Conditions, page SC14—11.1.6.1 Owner's Protective Liability coverage shall not be applicable for this project.
7. In Supplementary Conditions, page SC19—second paragraph referencing flood coverage is not applicable for this project.
8. In the specs, Section 1740 Warranties and Bonds, sheet 01740-3 under Part 3 Schedules of Warranties refers to Section 07530 - Roofing Systems. This is not applicable to this project.
9. Section 10425-Signs that was provided in addendum #1 was missing the information regarding the exterior signage. Please see the attached specification that has the added verbiage for the exterior signs as follows: *Material & Finish - #20 Acrylic Baked Enamel Letters and Custom Gibbsland Shield as shown on the exterior elevations. Manufactured by Metal Arts, Division of L & H Mfg. Co. & The Southwell Co. or an approved equal. (Refer to Architectural Drawings for locations, sizes and colors) Provide proper mounting screws and devices for the locations of letters. Font of letters shall match the existing signage on the Gibbsland Bank & Trust Hwy 80 branch location.*
10. Item 21 of addendum #1 states for the contractor to *Provide an allowance for the light fixtures labeled 'D' and 'H' based on the fixtures specified by Progress.* To clarify, the general contractor shall bid the fixtures as specified. However, after a contractor is selected and construction begins, the client shall be allowed to select different fixtures within that allowance prior to the fixtures being ordered.

## **SECTION 10425 - SIGNS**

### **PART ONE - GENERAL**

#### **DESCRIPTION**

Provide and install all signs indicated on drawings and specified herein.

Include all clips, supports, screws and mounting brackets for complete installation.

#### **RELATED WORK SPECIFIED ELSEWHERE**

General & Supplementary Conditions

#### **SUBMITTALS**

Submit manufacturers descriptive brochures and necessary supplemental detailed information indicating quality, finishes and accessories required for complete installation.

Camera ready layout shall be prepared by the manufacturer of graphic panel directory and approved by Architect prior to fabrication.

Architect shall select colors from manufacturers full range of colors.

#### **PRODUCT DELIVERY, STORAGE, AND HANDLING**

Deliver items in manufacturers original unopened protective packaging.

Store materials in original protective packaging to prevent soiling, physical damage or wetting.

Handle so as to prevent damage to finished surfaces.

### **PART TWO - PRODUCTS**

#### **MATERIALS**

##### **INTERIOR**

ROOM SIGNS & Miscellaneous: Series 1300 (A, B) Wood Frame System manufactured by Best Manufacturing Company or an approved equivalent by Kroy or National Signage Affiliates. Shall conform to ADA requirements.

Provide signs @ (3) restrooms

##### **EXTERIOR**

Material & Finish - #20 Acrylic Baked Enamel Letters and Custom Giblsand Shield as

shown on the exterior elevations. Manufactured by Metal Arts, Division of L & H Mfg. Co. & The Southwell Co. or an approved equal. (Refer to Architectural Drawings for locations, sizes and colors) Provide proper mounting screws and devices for the locations of letters. Font of letters shall match the existing signage on the Gibbsland Bank & Trust Hwy 80 branch location.

### **PART THREE - EXECUTION**

#### **INSPECTION**

Inspect surfaces to verify suitability.

Do not proceed until all conditions are acceptable.

#### **INSTALLATION**

Provide all mounting devices for complete installation.

Install all signs at all locations scheduled on Drawings.

Install all signs as per manufacturers recommendations and as indicated on drawings.

**END OF SECTION 10425**